



Work Order Bid (ID)

WORK ORDER INFORMATION

Work Order Name: WO/1002673/2

Work Order Type: Weatherization

Audit Name: 1000121

CLIENT INFORMATION

Client ID: 1002673

Alt. Client ID: C1002722SA101

AGENCY INFORMATION

Agency: Upper East Tennessee Human
Development Agency

Address: 301 Louis Street
Kingsport TN 37662

Agency Phone: 1-423-246-6180

Agency Fax:

Email Address: smeade@UETHDA.org

Company Name & License Number: _____

Contractor's Signature: _____

COMMENT

804 SQUARE FOOT RANCH BUILT ON A CRAWL SPACE IN 1957 WITH AN METAL ROOF.
ALL WORK TO BE DONE IN ACCORDANCE WITH THE TENNESSEE STANDARD WORK SPECIFICATIONS
AS ADOPTED BY THE TENNESSEE HOUSING DEVELOPMENT AGENCY.

CONTRACTOR IS RESPONSIBLE TO VERIFY DIMENSIONS AND SCOPE OF WORK PRIOR TO BID.

SURVEY ON 12/21/2018 BY RON CARLISLE (423) 736-0678
INITIAL BLOWER DOOR 3488@-50
POST WORK TARGET OF 1206@-50 MUST BE MET OR EXCEEDED
Contractor required to observe both RRP rule and LSW practices.
RRP Certified Firm/Renovator Required
Sullivan County

Measure Infiltration Redctn

Components

Inspected

Comment Initial Blower Door Reading: 3488@-50
 Post Work Target of 1206@-50 Must Be Met or Exceeded
 Suggested Best Practice of Air Infiltration Reduction is to use two-part foam and appropriate materials to seal the penetrations and openings in the Sub-floor (accessible in the crawl space) and in the ceilings (accessible in the attic).
 If applicable- rake back existing insulation and use two-part foam to seal the top plates of the walls. Use Rigid Foam Board and two-part foam to close and seal openings and penetrations of soffits, chases, and duct perimeters.

#	Material/Labour	Description/Comment	Unit	Qty	Estimated		Actual			
					Unit Cost	Total	Qty	Unit Cost	Total	
1	Miscellaneous Supplies	Infiltration Reduction	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
Other Detail										
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
Measure Sub Total						<input type="text"/>	Sub Total			<input type="text"/>

Field Notes:

Measure DWH Pipe Insulation

Components

Inspected

Comment INSULATE THE FIRST 6 FEET OF HOT AND COLD-WATER PIPE OUT OF THE WATER HEATER AS PER THE TN SWS

#	Material/Labour	Description/Comment	Unit	Qty	Estimated		Actual			
					Unit Cost	Total	Qty	Unit Cost	Total	
1	Insulation	DHW Pipe Insulation	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
2	Labor	DHW Pipe Insulation	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
Other Detail										
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
Measure Sub Total						<input type="text"/>	Sub Total			<input type="text"/>

Field Notes:

Measure DWH Tank Insulation

Components

Inspected

Comment AS PER THE TN SWS- Wrap the 30 Gallon Electric Water Heater With R-10 or Better Insulation. Secure with Tape and Zip Ties.

#	Material/Labour	Description/Comment	Unit	Estimated			Actual		
				Qty	Unit Cost	Total	Qty	Unit Cost	Total
1	Hot Water Equipment	DHW Tank Insulation	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
2	Labor	DHW Tank Insulation	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

Other Detail

<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

Measure Sub Total Sub Total

Field Notes:

Measure Replace A/C

Components AC1

Inspected

Comment REPLACE THE WINDOW AIR CONDITIONER WITH A NEW 8 Kbtu ENERGY STAR WINDOW AIR CONDITIONER.

#	Material/Labour	Description/Comment	Unit	Estimated			Actual		
				Qty	Unit Cost	Total	Qty	Unit Cost	Total
1	Cooling Equipment	Window A/C -	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
2	Labor	Window A/C -	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

Other Detail

<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

Measure Sub Total Sub Total

Field Notes:

Measure Wall Insulation

Components E1,N1,N2,S1,W1,W2

Inspected

Comment Contractor must use a dense pack blowing machine. Using fill tube, 100% of each cavity will be filled to a consistent density:
Cellulose material will be installed to a minimum density of 3.5 pounds per cubic foot

Install Chair Rail at the appropriate height to cover the plugs to be installed in the holes that are created to facilitate insulation installation.

#	Material/Labour	Description/Comment	Unit	Qty	Estimated		Actual		
					Unit Cost	Total	Qty	Unit Cost	Total
1	Insulation	Wall Insulation - Blown Cellulose - 2x4 Filled	SqFt	758.44	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
2	Labor	Wall Insulation - Blown Cellulose - 2x4 Filled	SqFt	758.44	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

Other Detail

<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

Measure Sub Total **Sub Total**

Field Notes:

Measure Attic Ins. R-19

Components A1

Inspected

Comment INCREASE THE EXISTING ATTIC INSULATION TO A CONSISTENT 16 INCH DEPTH WITH BLOWN FIBERGLASS. FOLLOW THE TENNESSEE STANDARD WORK SPECIFICATIONS

All electrical junction boxes will be flagged to be seen above the level of the insulation. Open electrical junction boxes will have covers installed. Insulation dams and enclosures will be installed as required

Insulation will be adequately marked for depth a minimum of every 300 square feet of attic area.

CREATE AN ATTIC ACCESS
INSTALL AN ENERGY LID OVER THE ATTIC ACCESS – W/S AND INSULATE

#	Material/Labour	Description/Comment	Unit	Estimated			Actual		
				Qty	Unit Cost	Total	Qty	Unit Cost	Total
1	Insulation	Attic Insulation - Blown Fiberglass - R-19	SqFt	804	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
2	Labor	Attic Insulation - Blown Fiberglass - R-19	SqFt	804	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
Other Detail									
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
Measure Sub Total						<input type="text"/>	Sub Total		<input type="text"/>

Field Notes:

Measure CO Monitor is Needed

Components

Inspected

Comment INSTALL A CO MONITOR AS PER THE TN SWS

#	Material/Labour	Description/Comment	Unit	Estimated			Actual			
				Qty	Unit Cost	Total	Qty	Unit Cost	Total	
1	Health and Safety Items	CO monitor	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
2	Labor	Labor	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
Other Detail										
	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
Measure Sub Total						<input type="text"/>	Sub Total			<input type="text"/>

Field Notes:

Measure Fix Improper Venting (Clothes Dryer)

Components

Inspected

Comment VENT THE CLOTHES DRYER AS PER THE TN SWS

#	Material/Labour	Description/Comment	Unit	Estimated			Actual			
				Qty	Unit Cost	Total	Qty	Unit Cost	Total	
1	Health and Safety Items	Equipment	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
2	Labor	Labor	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
Other Detail										
	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
Measure Sub Total						<input type="text"/>	Sub Total			<input type="text"/>

Field Notes:

Measure Fix Wiring Problems
(Basement/Crawlspace)

Components

Inspected

Comment INSTALL A JUNCTION BOX AT THE WATER HEATER ELECTRICAL CONNECTION

#	Material/Labour	Description/Comment	Unit	Estimated			Actual		
				Qty	Unit Cost	Total	Qty	Unit Cost	Total
1	Health and Safety Items	Equipment	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
2	Labor	Labor	Hour	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

Other Detail

<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

Measure Sub Total **Sub Total**

Field Notes:

Measure Install Bathroom Exhaust Fan

Components

Inspected

Comment INSTALL BATH FAN WITH A NEW TWO SPEED ASHRAE COMPLIANT FAN. SET TO 40 CFM CONTINUOUS. VENT TO THE OUTSIDE WITH A TRIM KIT AS PER THE TN SWS.

*****INSTALL A 6' VENT PIPE TO ENSURE PROPER VENTILATION*****

#	Material/Labour	Description/Comment	Unit	Estimated			Actual		
				Qty	Unit Cost	Total	Qty	Unit Cost	Total
1	Health and Safety Items	Bathroom exhaust fan	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
2	Labor	Labor	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

Other Detail

<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

Measure Sub Total **Sub Total**

Field Notes:

Measure Practice Lead Safe Weatherization (Walls)

Components

Inspected

Comment PRACTICE LEAD SAFE WEATHERIZATION- SUBMIT PICTURES TO THE AGENCY WITH CONTRACTOR INVOICE

#	Material/Labour	Description/Comment	Unit	Qty	Estimated		Actual			
					Unit Cost	Total	Qty	Unit Cost	Total	
1	Health and Safety Items	Practice Lead Safety	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
2	Labor	Labor	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
Other Detail										
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
Measure Sub Total						<input type="text"/>	Sub Total			<input type="text"/>

Field Notes:

Measure PressureRelief Piping Needed

Components

Inspected

Comment INSTALL A PRESSURE RELIEF PIPE EXTENSION AS PER THE TN SWS

#	Material/Labour	Description/Comment	Unit	Qty	Estimated		Actual			
					Unit Cost	Total	Qty	Unit Cost	Total	
1	Health and Safety Items	Pressure relief piping	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
2	Labor	Labor	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
Other Detail										
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
Measure Sub Total						<input type="text"/>	Sub Total			<input type="text"/>

Field Notes:

Measure *Smoke Detector is Needed*

Components

Inspected

Comment INSTALL TWO SMOKE DETECTORS AS PER THE TN SWS

#	Material/Labour	Description/Comment	Unit	Qty	Estimated		Actual			
					Unit Cost	Total	Qty	Unit Cost	Total	
1	Health and Safety Items	Smoke detector	Each	2	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
2	Labor	Labor	Each	2	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
Other Detail										
	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
Measure Sub Total						<input type="text"/>	Sub Total			<input type="text"/>

Field Notes:

Measure *Vapor Barrier Needed (Basement/Crawlspace)*

Components

Inspected

Comment INSTALL 6 MIL BLACK POLY VAPOR BARRIER AS PER THE TN SWS.

THIS MEASURE REFERS TO THE SPACE WHERE VAPOR BARRIER IS ABLE TO BE INSTALLED- COVER GROUND THE REAR TWO SECTIONS OF CRAWL SPACE AND WHERE PRACTICAL IN DUG OUT BASEMENT

#	Material/Labour	Description/Comment	Unit	Qty	Estimated		Actual			
					Unit Cost	Total	Qty	Unit Cost	Total	
1	Health and Safety Items	Basement / crawlspace vapor barrier	SqFt	980	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
2	Labor	Labor	SqFt	980	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
Other Detail										
	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
Measure Sub Total						<input type="text"/>	Sub Total			<input type="text"/>

Field Notes:

Work Ordere Grand Total:

Grand Total: