



## Work Order Bid (ID)

---

### **WORK ORDER INFORMATION**

**Work Order Name:** WO/1001273/1

**Work Order Type:** Weatherization

**Audit Name:** 1002507

### **CLIENT INFORMATION**

**Client ID:** 1001273

**Alt. Client ID:** C1001281SA101

**County:** Greene

### **AGENCY INFORMATION**

**Agency:** Upper East Tennessee Human  
Development Agency

**Address:** 301 Louis Street  
Kingsport TN 37662

**Agency Phone:** 1-423-246-6180

**Agency Fax:**

**Email Address:** sdawes@uethda.org

**Company Name & License Number:** \_\_\_\_\_

**Contractor's Signature:** \_\_\_\_\_

### **COMMENT**

938 SQUARE FOOT SINGE WIDE MOBILE HOME MANUFACTURED IN 1982.  
ALL WORK TO BE DONE IN ACCORDANCE WITH THE TENNESSEE STANDARD WORK SPECIFICATIONS  
AS ADOPTED BY THE TENNESSEE HOUSING DEVELOPMENT AGENCY.

CONTRACTOR IS RESPONSIBLE TO VERIFY DIMENSIONS AND SCOPE OF WORK PRIOR TO BID.

SURVEY ON 6/12/2020 BY RON CARLISLE (423) 736-0678  
INITIAL BLOWER DOOR 2313 @-50  
POST WORK TARGET 938 @-50 MUST BE REACHED OR EXCEEDED

**Measure 1 General Air Sealing**

**Components**

**Inspected**

**Comment** Initial Blower Door Reading: 2313 @-50  
 Post Work Target of 938 @-50 Must Be Met or Exceeded  
 Suggested Best Practice of Air Infiltration Reduction is to use two-part foam and appropriate materials to seal the penetrations and openings in the Sub-floor (accessible in the crawl space) and in the ceilings (accessible in the attic).  
 If applicable- rake back existing insulation and use two-part foam to seal the top plates of the walls. Use Rigid Foam Board and two-part foam to close and seal openings and penetrations of soffits, chases, and duct perimeters.

#	Material/Labour	Description/Comment	Unit	Qty	Estimated		Actual			
					Unit Cost	Total	Qty	Unit Cost	Total	
1	Insulation	General air sealing (setup cost)	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
2	Miscellaneous Supplies	Infiltration Reduction	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
<b>Other Detail</b>										
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
<b>Measure Sub Total</b>						<input type="text"/>	<b>Sub Total</b>			<input type="text"/>

**Field Notes:**

**Measure 2 DWH Pipe Insulation**

**Components**

**Inspected**

**Comment** INSULATE THE FIRST 6 FEET OF HOT AND COLD-WATER PIPE OUT OF THE WATER HEATER AS PER THE TN SWS

#	Material/Labour	Description/Comment	Unit	Qty	Estimated		Actual			
					Unit Cost	Total	Qty	Unit Cost	Total	
1	Insulation	DWH Pipe Insulation	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
2	Labor	DWH Pipe Insulation	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
<b>Other Detail</b>										
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
<b>Measure Sub Total</b>						<input type="text"/>	<b>Sub Total</b>			<input type="text"/>

**Field Notes:**

**Measure 3 DWH Tank Insulation**

**Components**

**Inspected**

**Comment** AS PER THE TN SWS- Wrap the 40 Gallon Electric Water Heater With R-10 or Better Insulation. Secure with Tape and Zip Ties.

#	Material/Labour	Description/Comment	Unit	Estimated			Actual		
				Qty	Unit Cost	Total	Qty	Unit Cost	Total
1	Insulation	DWH Tank Insulation	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
2	Labor	DWH Tank Insulation	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
<b>Other Detail</b>									
	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
<b>Measure Sub Total</b>						<input type="text"/>	<b>Sub Total</b>		<input type="text"/>

**Field Notes:**

**Measure 4 CO Monitor is Needed**

**Components**

**Inspected**

**Comment** INSTALL A CO MONITOR AS PER THE TN SWS

#	Material/Labour	Description/Comment	Unit	Estimated			Actual		
				Qty	Unit Cost	Total	Qty	Unit Cost	Total
1	Health and Safety Items	CO monitor	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
2	Labor	Labor	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
<b>Other Detail</b>									
	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
<b>Measure Sub Total</b>						<input type="text"/>	<b>Sub Total</b>		<input type="text"/>

**Field Notes:**

**Measure 5      Fix Gas Leak Present**

**Components**

**Inspected**

**Comment**

Client Reported Possible Propane Leak- The Tank Was Empty at the Time of the Audit- Contact the client with notice of work schedule to allow them to get a small amount of propane so that leak can be detected and repaired.

#	Material/Labour	Description/Comment	Unit	Qty	Estimated		Actual			
					Unit Cost	Total	Qty	Unit Cost	Total	
1	Health and Safety Items	Equipment	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
2	Labor	Labor	Hour	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
<b>Other Detail</b>										
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
<b>Measure Sub Total</b>						<input type="text"/>	<b>Sub Total</b>			<input type="text"/>

**Field Notes:**

**Measure 6      Fix Improper Venting (Clothes Dryer)**

**Components**

**Inspected**

**Comment**

VENT THE CLOTHES DRYER AS PER THE TN SWS- INSULATE IN THE VENT PIPE IN UNCONDITIONED SPACES

#	Material/Labour	Description/Comment	Unit	Qty	Estimated		Actual			
					Unit Cost	Total	Qty	Unit Cost	Total	
1	Health and Safety Items	Equipment	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
2	Labor	Labor	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
<b>Other Detail</b>										
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
<b>Measure Sub Total</b>						<input type="text"/>	<b>Sub Total</b>			<input type="text"/>

**Field Notes:**

**Measure 7 Install Bathroom Exhaust Fan**

**Components**

**Inspected**

**Comment** INSTALL A NEW TWO SPEED ASHRAE COMPLIANT FAN. SET TO 40 CFM CONTINUOUS. VENT TO THE OUTSIDE WITH A TRIM KIT AS PER THE TN SWS.

#	Material/Labour	Description/Comment	Unit	Estimated			Actual		
				Qty	Unit Cost	Total	Qty	Unit Cost	Total
1	Health and Safety Items	Bathroom exhaust fan	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
2	Labor	Labor	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

**Other Detail**

<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

**Measure Sub Total**  **Sub Total**

**Field Notes:**

**Measure 8 PressureRelief Piping Needed**

**Components**

**Inspected**

**Comment** INSTALL A PRESSURE RELIEF PIPE EXTENSION AS PER THE TN SWS- EXTEND TO OUTSIDE OF THE FOUNDATION, TURN DOWN WITH AN ELBOW AND TERMINATE THE PIPE TO WITHIN 6" OF EXTERIOR GRADE.

#	Material/Labour	Description/Comment	Unit	Estimated			Actual		
				Qty	Unit Cost	Total	Qty	Unit Cost	Total
1	Health and Safety Items	Pressure relief piping	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
2	Labor	Labor	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

**Other Detail**

<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

**Measure Sub Total**  **Sub Total**

**Field Notes:**

**Measure 9 Smoke Detector is Needed**

**Components**

**Inspected**

**Comment** INSTALL SMOKE DETECTORS IN ALL BEDROOMS

#	Material/Labour	Description/Comment	Unit	Qty	Estimated		Actual			
					Unit Cost	Total	Qty	Unit Cost	Total	
1	Health and Safety Items	Smoke detector	Each	3	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
2	Labor	Labor	Each	3	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
<b>Other Detail</b>										
	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
<b>Measure Sub Total</b>						<input type="text"/>	<b>Sub Total</b>			<input type="text"/>

**Field Notes:**

<b>Work Ordere Grand Total:</b>	<input type="text"/>	<b>Grand Total:</b>	<input type="text"/>
---------------------------------	----------------------	---------------------	----------------------