



Work Order Bid (ID)

WORK ORDER INFORMATION

Work Order Name: WO/1003697/1

Work Order Type: Weatherization

Audit Name: 1003018

CLIENT INFORMATION

Client ID: 1003697

Alt. Client ID: C1003781SA101

County: Hawkins

AGENCY INFORMATION

Agency: Upper East Tennessee Human
Development Agency

Address: 301 Louis Street
Kingsport TN 37662

Agency Phone: 1-423-246-6180

Agency Fax:

Email Address: sdawes@uethda.org

Company Name & License Number: _____

Contractor's Signature: _____

COMMENT

832 SQUARE FOOT RANCH BUILT ON A CRAWL SPACE IN 1933 WITH A METAL ROOF.
ALL WORK TO BE DONE IN ACCORDANCE WITH THE TENNESSEE STANDARD WORK SPECIFICATIONS
AS ADOPTED BY THE TENNESSEE HOUSING DEVELOPMENT AGENCY.

CONTRACTOR IS RESPONSIBLE TO VERIFY DIMENSIONS AND SCOPE OF WORK PRIOR TO BID.

SURVEY ON 9/24/2020 BY RON CARLISLE (423) 736-0678
INITIAL BLOWER DOOR 3018@-50
POST WORK TARGET OF 1248@-50 MUST BE MET OR EXCEEDED
Contractor required to observe both RRP rule and LSW practices.
RRP Certified Firm/Renovator Required

Measure 1 Crawl Space Door

Components

Inspected

Comment INSTALL A CRAWL SPACE ACCESS DOOR- THE OPENING EXISTS. APPLY TWO COATS OF PAINT AND MECHANICAL FASTENERS.

#	Material/Labour	Description/Comment	Unit	Estimated			Actual		
				Qty	Unit Cost	Total	Qty	Unit Cost	Total
1	Construction Materials/Hardware	Crawl Space Door	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
2	Labor	Labor	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

Other Detail

<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

Measure Sub Total **Sub Total**

Field Notes:

Measure 2 Infiltration Redctn

Components

Inspected

Comment Initial Blower Door Reading:3018@-50
 Post Work Target of 1248 @-50 Must Be Met or Exceeded
 Suggested Best Practice of Air Infiltration Reduction is to use two-part foam and appropriate materials to seal the penetrations and openings in the Sub-floor (accessible in the crawl space) and in the ceilings (accessible in the attic).
 If applicable- rake back existing insulation and use two-part foam to seal the top plates of the walls. Use Rigid Foam Board and two-part foam to close and seal openings and penetrations of soffits, chases, and duct perimeters.

#	Material/Labour	Description/Comment	Unit	Estimated			Actual		
				Qty	Unit Cost	Total	Qty	Unit Cost	Total
1	Miscellaneous Supplies	Infiltration Reduction	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

Other Detail

<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

Measure Sub Total **Sub Total**

Field Notes:

Measure 3 DWH Pipe Insulation

Components

Inspected

Comment INSULATE THE FIRST 6 FEET OF HOT AND COLD-WATER PIPE OUT OF THE WATER HEATER AS PER THE TN SWS

#	Material/Labour	Description/Comment	Unit	Estimated			Actual		
				Qty	Unit Cost	Total	Qty	Unit Cost	Total
1	Insulation	DHW Pipe Insulation	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
2	Labor	DHW Pipe Insulation	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
Other Detail									
	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
Measure Sub Total						<input type="text"/>	Sub Total		<input type="text"/>

Field Notes:

Measure 4 DWH Tank Insulation

Components

Inspected

Comment AS PER THE TN SWS- Wrap the 40 Gallon Electric Water Heater With R-10 or Better Insulation. Secure with Tape and Zip Ties.

#	Material/Labour	Description/Comment	Unit	Estimated			Actual		
				Qty	Unit Cost	Total	Qty	Unit Cost	Total
1	Hot Water Equipment	DHW Tank Insulation	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
2	Labor	DHW Tank Insulation	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
Other Detail									
	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
Measure Sub Total						<input type="text"/>	Sub Total		<input type="text"/>

Field Notes:

Measure 5 Attic Ins. R-30

Components A1

Inspected

Comment INCREASE THE EXISTING ATTIC INSULATION TO A CONSISTENT 16 INCH DEPTH WITH BLOWN FIBERGLASS. FOLLOW THE TENNESSEE STANDARD WORK SPECIFICATIONS

All electrical junction boxes will be flagged to be seen above the level of the insulation. Open electrical junction boxes will have covers installed. Insulation dams and enclosures will be installed as required

Insulation will be adequately marked for depth a minimum of every 300 square feet of attic area.

INSTALL AN ENERGY LID OVER THE ATTIC ACCESS – W/S AND INSULATE

116 LINEAR FEET OF BAFFLES NEEDED BETWEEN RAFTERS @19 O.C. 6/12 PITCH

#	Material/Labour	Description/Comment	Unit	Qty	Estimated		Actual		
					Unit Cost	Total	Qty	Unit Cost	Total
1	Insulation	Attic Insulation - Blown Fiberglass - R-30	SqFt	832	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
2	Labor	Attic Insulation - Blown Fiberglass - R-30	SqFt	832	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

Other Detail

<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

Measure Sub Total **Sub Total**

Field Notes:

Measure 6 Refrigerator Rplcmnt

Components

Inspected

Comment Replace the Existing Refrigerator with a New 21 Cubic Foot Energy Star Refrigerator. Hinge the Door Appropriately.

Remove and Properly Dispose of the Old Refrigerator.

#	Material/Labour	Description/Comment	Unit	Estimated			Actual			
				Qty	Unit Cost	Total	Qty	Unit Cost	Total	
1	Refrigerators	Any - 21 CU FT	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
Other Detail										
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
Measure Sub Total						<input type="text"/>	Sub Total			<input type="text"/>

Field Notes:

Measure 7 40G Electric Water Heater (UEF .93)

Components

Inspected

Comment REMOVE AND REPLACE THE LEAKING 40 GALLON ELECTRIC WATER HEATER WITH A NEW 40 GALLON .95 ENERGY FACTOR WATER HEATER. INSTALL AS PER THE TN SWS, WITH PAN, EXPANSION TANK AND PRESSURE RELIEF PIPE WITHIN 6 INCHES OF THE DRAIN PAN. EXTEND THE PIPE FROM THE PAN TO THE OUTSIDE OF THE FOUNDATION. REMOVE AND PROPERLY DISPOSE OF THE OLD WATER HEATER.

#	Material/Labour	Description/Comment	Unit	Estimated			Actual			
				Qty	Unit Cost	Total	Qty	Unit Cost	Total	
1	Construction Materials/Hardware	Equipment	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
2	Labor	Labor	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
Other Detail										
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
Measure Sub Total						<input type="text"/>	Sub Total			<input type="text"/>

Field Notes:

Measure 8 CO Monitor is Needed

Components

Inspected

Comment INSTALL A CO MONITOR AS PER THE TN SWS

#	Material/Labour	Description/Comment	Unit	Qty	Estimated		Actual			
					Unit Cost	Total	Qty	Unit Cost	Total	
1	Health and Safety Items	CO Detector	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
2	Labor	Labor	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
Other Detail										
	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
Measure Sub Total						<input type="text"/>	Sub Total			<input type="text"/>

Field Notes:

Measure 9 Fix Improper Venting (Clothes Dryer)

Components

Inspected

Comment VENT THE CLOTHES DRYER AS PER THE TN SWS- INSULATE IN THE VENT PIPE IN UNCONDITIONED SPACES

#	Material/Labour	Description/Comment	Unit	Qty	Estimated		Actual			
					Unit Cost	Total	Qty	Unit Cost	Total	
1	Construction Materials/Hardware	Equipment	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
2	Labor	Labor	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
Other Detail										
	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
Measure Sub Total						<input type="text"/>	Sub Total			<input type="text"/>

Field Notes:

Measure 10 Fix Wiring Problems (Attic)

Components

Inspected

Comment APPROXIMATELY 10 JUNCTION BOXES NEEDED IN THE ATTIC
 All EXISTING electrical junction boxes will be flagged to be seen above the level of the insulation.
 Open electrical junction boxes will have covers installed. Insulation dams and enclosures will be installed as required.

RE-ATTACH THE LIGHT FIXTURES IN THE BEDROOMS- HANGING BY WIRES

#	Material/Labour	Description/Comment	Unit	Qty	Estimated		Actual		
					Unit Cost	Total	Qty	Unit Cost	Total
1	Health and Safety Items	Equipment	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
2	Labor	Labor	Hour	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
Other Detail									
	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
Measure Sub Total						<input type="text"/>	Sub Total		<input type="text"/>

Field Notes:

Measure 11 Fix Wiring Problems (Walls)

Components

Inspected

Comment INSTALL WEATHERPROOF JUNCTION BOXES AND COVERS WHERE NEEDED ON THE EXTERIOR WIRE CONNECTIONS

INSTALL A JUNCTION BOX IN THE WALL, OVER THE EXPOSED WIRE ENDS OVER THE STOVE

#	Material/Labour	Description/Comment	Unit	Qty	Estimated		Actual			
					Unit Cost	Total	Qty	Unit Cost	Total	
1	Health and Safety Items	Equipment	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
2	Labor	Labor	Hour	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
Other Detail										
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
Measure Sub Total						<input type="text"/>	Sub Total			<input type="text"/>

Field Notes:

Measure 12 Guttering Replacement (per Linear Foot)

Components

Inspected

Comment REMOVE AND REPLACE THE GUTTERING WITH SEAMLESS GUTTERS AND DOWN SPOUTS- INSTALL TURN OUTS AND SPLASH BLOCKS TO DIRECT WATER AWAY FROM THE FOUNDATION

#	Material/Labour	Description/Comment	Unit	Qty	Estimated		Actual			
					Unit Cost	Total	Qty	Unit Cost	Total	
1	Construction Materials/Hardware	Guttering Replacement (per Linear Foot)	Linear Foot	160	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
2	Labor	Labor	Linear Foot	160	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
Other Detail										
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
Measure Sub Total						<input type="text"/>	Sub Total			<input type="text"/>

Field Notes:

Measure 13 Heatpump -2 Ton / 24 KBtu/h (Package) Components

Inspected

Comment INSTALL A NEW 24 Kbtu PACKAGED DUAL FUEL HEAT PUMP WITH A 45 KBTU PROPANE AUXILLARY/EMERGENCY SYSTEM. NEW GAS LINE REQUIRED. SUPPLY HOME OWNER WITH 12 RETURN FILTERS

Mechanical permits will be required for all HVAC work, as per local code. All Heat pumps installed to be 15 SEER, 8.5 HSPF. All cooling equipment, ENERGY STAR labeled and shall be sized according to the latest editions of ACCA Manuals J and S .Specification of any type of heating unit shall be taken to include all connections, wiring, ducting, safety switches, thermostats, pad if existing does not fit new unit and all other work to provide a complete, Tight, efficient, balanced and operational system. All wiring shall be on separate circuits, wired from panel box or disconnects to HVAC unit by contractor. If installing a split system that does not have existing line set the cost should be included in bid to provide new line set. If leaving the existing line set the line is to be flushed and pressurized to insure no leakage. If installing a package unit, it is to include a four-sided shroud. All work to meet current code for city or county work is being performed. Must provide all warranty information with invoice. If unit warranty needs registered with factory contractor is to do this for client.

#	Material/Labour	Description/Comment	Unit	Qty	Estimated		Actual			
					Unit Cost	Total	Qty	Unit Cost	Total	
1	Construction Materials/Hardware	Equipment	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
2	Labor	Labor	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
Other Detail										
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
Measure Sub Total						<input type="text"/>	Sub Total			<input type="text"/>

Field Notes:

Measure 14 Install Bathroom Exhaust Fan (ASHRAE)

Components

Inspected

Comment REPLACE THE EXISTING BATH FAN/LIGHT COMBINATION WITH A NEW TWO SPEED ASHRAE COMPLIANT FAN/LIGHT COMBINATION. SET TO 40 CFM CONTINUOUS. VENT TO THE OUTSIDE WITH A TRIM KIT AS PER THE TN SWS.

*****INSTALL A 6' VENT PIPE TO ENSURE PROPER VENTILATION*****

#	Material/Labour	Description/Comment	Unit	Qty	Estimated		Actual			
					Unit Cost	Total	Qty	Unit Cost	Total	
1	Construction Materials/Hardware	Bathroom Exhaust Fan (ASHRAE)	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
2	Labor	Labor	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
Other Detail										
	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
Measure Sub Total						<input type="text"/>	Sub Total			<input type="text"/>

Field Notes:

Measure 15 New Duct System

Components

Inspected

Comment INSTALL A NEW DUCT SYSTEM- SUBMIT MANUAL D WITH INVOICE

#	Material/Labour	Description/Comment	Unit	Qty	Estimated		Actual			
					Unit Cost	Total	Qty	Unit Cost	Total	
1	Construction Materials/Hardware	New Duct System	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
2	Labor	Labor	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
Other Detail										
	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
Measure Sub Total						<input type="text"/>	Sub Total			<input type="text"/>

Field Notes:

Measure 16 Smoke Detector is Needed

Components

Inspected

Comment INSTALL SMOKE DETECTORS IN ALL BEDROOMS AND COMMON AREA (HALLWAY)

#	Material/Labour	Description/Comment	Unit	Qty	Estimated		Actual			
					Unit Cost	Total	Qty	Unit Cost	Total	
1	Health and Safety Items	Smoke Detector	Each	4	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
2	Labor	Labor	Hour	4	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
Other Detail										
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
Measure Sub Total						<input type="text"/>	Sub Total			<input type="text"/>

Field Notes:

Measure 17 Vapor Barrier Needed (Basement/Crawlspace)

Components

Inspected

Comment INSTALL 6 MIL BLACK POLY VAPOR BARRIER AS PER THE TN SWS. SEAL THE SEAMS WITH MASTIC. LAP UP AND ATTACH TO THE WALLS AND PIERS

#	Material/Labour	Description/Comment	Unit	Qty	Estimated		Actual			
					Unit Cost	Total	Qty	Unit Cost	Total	
1	Construction Materials/Hardware	Vapor Barrier	SqFt	956	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
2	Health and Safety Items		SqFt	956	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
Other Detail										
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
Measure Sub Total						<input type="text"/>	Sub Total			<input type="text"/>

Field Notes:

Work Ordere Grand Total:	<input type="text"/>	Grand Total:	<input type="text"/>
---------------------------------	----------------------	---------------------	----------------------