



Work Order Bid (ID)

WORK ORDER INFORMATION

Work Order Name: WO/1003704/1

Work Order Type: Weatherization

Audit Name: 1002664

CLIENT INFORMATION

Client ID: 1003704

Alt. Client ID: C1003788SA101

County: Washington

AGENCY INFORMATION

Agency: Upper East Tennessee Human
Development Agency

Address: 301 Louis Street
Kingsport TN 37662

Agency Phone: 1-423-246-6180

Agency Fax:

Email Address: sdawes@uethda.org

Company Name & License Number: _____

Contractor's Signature: _____

COMMENT

864 SQUARE FOOT RANCH BUILT ON A CRAWL SPACE IN 2009 WITH AN ASPHALT SHINGLE ROOF.
ALL WORK TO BE DONE IN ACCORDANCE WITH THE TENNESSEE STANDARD WORK SPECIFICATIONS
AS ADOPTED BY THE TENNESSEE HOUSING DEVELOPMENT AGENCY.

CONTRACTOR IS RESPONSIBLE TO VERIFY DIMENSIONS AND SCOPE OF WORK PRIOR TO BID.

SURVEY ON 6/9/2020 BY RON CARLISLE (423) 736-0678
INITIAL BLOWER DOOR 2451 @-50
POST WORK TARGET OF 864 @-50 MUST BE MET OR EXCEEDED

Measure 1 Attic Access Door

Components

Inspected

Comment CREATE A NEW ATTIC ACCESS, INSTALL AN ENERGY LID OVER THE ATTIC ACCESS – W/S AND INSULATE

#	Material/Labour	Description/Comment	Unit	Estimated			Actual		
				Qty	Unit Cost	Total	Qty	Unit Cost	Total
1	Construction Materials/Hardware	Attic Access Door	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
2	Labor	Labor	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

Other Detail

<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

Measure Sub Total **Sub Total**

Field Notes:

Measure 2 Vapor Barrier Needed (Basement/Crawlspace)

Components

Inspected

Comment INSTALL 6 MIL BLACK POLY VAPOR BARRIER AS PER THE TN SWS. SEAL THE SEAMS WITH MASTIC. LAP UP AND ATTACH TO THE WALLS AND PIERS

#	Material/Labour	Description/Comment	Unit	Estimated			Actual		
				Qty	Unit Cost	Total	Qty	Unit Cost	Total
1	Health and Safety Items	Basement / crawlspace vapor barrier	SqFt	800	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
2	Labor	Labor	SqFt	800	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

Other Detail

<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

Measure Sub Total **Sub Total**

Field Notes:

Measure 3 Seal Ducts

Components

Inspected

Comment SHOP-VAC AND PREPARE THE DUCT-WORK AS PER THE TN SWS.
 USE MASTIC OR APPROPRIATE MATERIAL TO SEAL THE DUCT-WORK AS PER
 THE THDA SWS
 THE OBJECTIVE IS TO REDUCE THE PRESSURE PAN READINGS TO LESS THAN
 1 OR AS TIGHT AS POSSIBLE.
 PRESSURE PAN READINGS:
 RETURN 26.4
 LIVING ROOM 133
 KITCHEN 52.3
 BEDROOM 33.7
 BEDROOM- no access
 BATH ROOM 10.8

#	Material/Labour	Description/Comment	Unit	Estimated			Actual			
				Qty	Unit Cost	Total	Qty	Unit Cost	Total	
1	Miscellaneous Supplies	Duct Sealing	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
Other Detail										
	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
Measure Sub Total						<input type="text"/>	Sub Total			<input type="text"/>

Field Notes:

Measure 4 Infiltration Redctn

Components

Inspected

Comment Initial Blower Door Reading: 2451 @-50
 Post Work Target of 864 @-50 Must Be Met or Exceeded

SEAL THE EXISTING ATTIC ACCESS LOCATED IN THE CLOSET- INSULATE THE TOP TO R-30 OR BETTER

Suggested Best Practice of Air Infiltration Reduction is to use two-part foam and appropriate materials to seal the penetrations and openings in the Sub-floor (accessible in the crawl space) and in the ceilings (accessible in the attic).
 If applicable- rake back existing insulation and use two-part foam to seal the top plates of the walls. Use Rigid Foam Board and two-part foam to close and seal openings and penetrations of soffits, chases, and duct perimeters.

#	Material/Labour	Description/Comment	Unit	Estimated			Actual			
				Qty	Unit Cost	Total	Qty	Unit Cost	Total	
1	Miscellaneous Supplies	Infiltration Reduction	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
Other Detail										
	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
Measure Sub Total						<input type="text"/>	Sub Total			<input type="text"/>

Field Notes:

Measure 5 DWH Tank Insulation

Components

Inspected

Comment AS PER THE TN SWS- Wrap the 50 Gallon Electric Water Heater With R-10 or Better Insulation. Secure with Tape and Zip Ties.

#	Material/Labour	Description/Comment	Unit	Estimated			Actual		
				Qty	Unit Cost	Total	Qty	Unit Cost	Total
1	Hot Water Equipment	DHW Tank Insulation	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
2	Labor	DHW Tank Insulation	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

Other Detail

<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

Measure Sub Total **Sub Total**

Field Notes:

Measure 6 DWH Pipe Insulation

Components

Inspected

Comment INSULATE THE FIRST 6 FEET OF HOT AND COLD-WATER PIPE OUT OF THE WATER HEATER AS PER THE TN SWS

#	Material/Labour	Description/Comment	Unit	Estimated			Actual		
				Qty	Unit Cost	Total	Qty	Unit Cost	Total
1	Insulation	DHW Pipe Insulation	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
2	Labor	DHW Pipe Insulation	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

Other Detail

<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

Measure Sub Total **Sub Total**

Field Notes:

Measure 7 Floor Ins. R-19

Components F1

Inspected

Comment REMOVE AND REPLACE THE FALLEN FLOOR INSULATION 864 SQUARE FEET

INSTALL R-19 FIBERGLASS BATTS IN BETWEEN THE 2 X 8 FLOOR JOISTS @ 16 inches O.C. AS PER THE TN SWS.

#	Material/Labour	Description/Comment	Unit	Qty	Estimated		Actual		
					Unit Cost	Total	Qty	Unit Cost	Total
1	Insulation	Floor Insulation - Fiberglass Batts - R-19	SqFt	864	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
2	Labor	Floor Insulation - Fiberglass Batts - R-19	SqFt	864	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

Other Detail

<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

Measure Sub Total **Sub Total**

Field Notes:

Measure 8 CO Monitor is Needed

Components

Inspected

Comment INSTALL A CO MONITOR AS PER THE TN SWS

#	Material/Labour	Description/Comment	Unit	Qty	Estimated		Actual		
					Unit Cost	Total	Qty	Unit Cost	Total
1	Health and Safety Items	CO monitor	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
2	Labor	Labor	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

Other Detail

<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

Measure Sub Total **Sub Total**

Field Notes:

Measure 9 Fix Not Operational Bathroom Exhaust Components

Inspected

Comment REPLACE THE EXISTING BATH FAN/LIGHT COMBINATION WITH A NEW TWO SPEED ASHRAE COMPLIANT FAN/LIGHT COMBINATION. SET TO 40 CFM CONTINUOUS. VENT TO THE OUTSIDE WITH A TRIM KIT AS PER THE TN SWS.

*****INSTALL A 6' VENT PIPE TO ENSURE PROPER VENTILATION*****

#	Material/Labour	Description/Comment	Unit	Qty	Estimated		Actual			
					Unit Cost	Total	Qty	Unit Cost	Total	
1	Health and Safety Items	Equipment	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
2	Labor	Labor	Hour	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
Other Detail										
	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
Measure Sub Total						<input type="text"/>	Sub Total			<input type="text"/>

Field Notes:

Measure 10 Replace/Install New Heat Pump

Components

Inspected

Comment REPLACE THE ELECTRIC FURNACE AND CENTRAL AIR CONDITIONER WITH A NEW 24 Kbtu/h HEAT PUMP- RETRO-FIT TO EXISTING DUCT-WORK SUPPLY HOME OWNER WITH 12 RETURN FILTERS

Mechanical permits will be required for all HVAC work, as per local code. All Heat pumps installed to be 15 SEER, 8.5 HSPF. All cooling equipment, ENERGY STAR labeled and shall be sized according to the latest editions of ACCA Manuals J and S. Specification of any type of heating unit shall be taken to include all connections, wiring, ducting, safety switches, thermostats, pad if existing does not fit new unit and all other work to provide a complete, Tight, efficient, balanced and operational system. All wiring shall be on separate circuits, wired from panel box or disconnects to HVAC unit by contractor. If installing a split system that does not have existing line set the cost should be included in bid to provide new line set. If leaving the existing line set the line is to be flushed and pressurized to insure no leakage. Include condensate pump, if situation requires. If installing a package unit, it is to include a four-sided shroud. All work to meet current code for city or county work is being performed. Must provide all warranty information with invoice. If unit warranty needs registered with factory contractor is to do this for client.

#	Material/Labour	Description/Comment	Unit	Estimated			Actual		
				Qty	Unit Cost	Total	Qty	Unit Cost	Total
1	Unspecified	Misc Material	Each	1					
Other Detail									
Measure Sub Total							Sub Total		

Field Notes:

Measure 11 Smoke Detector is Needed

Components

Inspected

Comment INSTALL SMOKE DETECTORS IN ALL BEDROOMS AND COMMON AREA (HALLWAY)

#	Material/Labour	Description/Comment	Unit	Qty	Estimated		Actual			
					Unit Cost	Total	Qty	Unit Cost	Total	
1	Health and Safety Items	Smoke detector	Each	4	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
2	Labor	Labor	Each	4	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
Other Detail										
	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	
Measure Sub Total						<input type="text"/>	Sub Total			<input type="text"/>

Field Notes:

Work Ordere Grand Total:	<input type="text"/>	Grand Total:	<input type="text"/>
---------------------------------	----------------------	---------------------	----------------------